

R

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

JAN 13 1976

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company  
Complete Address 205 Litwin Bldg., Wichita, Kansas  
Lease Name Fox "A" Well No. 1  
Location 150° NE of C: NE NE Sec. 8 Twp. 20 Rge. (E) (W) 20  
County Pawnee Total Depth 4323'  
Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A XX  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Co. Tools  
Address \_\_\_\_\_ License No. \_\_\_\_\_  
Operation Completed: Hour 1:30 P Day 9 Month 1 Year 1976

The above well was plugged as follows:

RTD 4323' 8 5/8 csg set 204' cwc 125 sk. Plg. Mat. 50-50 poz 2% total gel.  
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.  
Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red Massey  
Well Plugging Supervisor

DATE 1-14-76

INV. NO. 2561-W