

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 - 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Appleton Oil Company

Complete Address: 506 Beacon Bldg., Tulsa, Oklahoma

Lease Name Fleming Well No. 1

Location C NW NE Sec. 32 Twp. 20 Rge. 17 (E) (W) X

County Pawnee Total Depth 4043

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: _____

Plugging Contractor: Sage Drlg. Co.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 4A Day 1 Month 10 Year 1968

The Above well was plugged as follows:

RTD 4043' 8 5/8 csg set at 249' cwc.

Gunned pitd, circulated heavy mud, set cementing plug at 500' and displaced 50 sc cmt. thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/4/68
INV. NO. 8574-14