

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Appleton Oil Company

Complete Address: 506 Beacon Bldg., Tulsa, Okla.

Lease Name Penicks Well No. 1

Location SW NE SE Sec. 29 Twp. 20 Rge. 17 (E) (W) X

County Pawnee Total Depth 4040

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drlg.

Address: Wichita, Ks. License No.

Operation Completed: Hour 4A Day 17 Month 7 Year 1968

The Above well was plugged as follows:

RTD 4040' 8 5/8 csg at 256' cwc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. J. Massey
Well Plugging Supervisor

INVOICED

DATE 7/19/68

INV. NO. 8142-W