

15.135.20150.0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name D. R. Lauck Oil Company

Complete Address: 301 S. Broadway Wichita, Kansas

Lease Name Rowland Well No. 2

Location C NW SW Sec. 24 Twp. 20 Rge. 21 (E) (W) X

County Ness Total Depth 4440

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 7:30 P Day 31 Month 5 Year 1968

The Above well was plugged as follows:

RTD 4440' 8 5/8 csg set at 314' cwc Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 6/4/68
INV. NO. 1879-W