

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth Nat'l Bk. Bldg., Wichita, Kansas

Lease Name Johnson "E" Well No. 1

Location C NE SW Sec. 17 Twp. 20 Rge. 23 (E) (W) X

County Ness Total Depth 4390'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Russ Casing Pulling Co. Inc.

Address: Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 11 A Day 13 Month 8 Year 1968

The Above well was plugged as follows:

Total Depth 4390' 8 5/8 csg set at 261' cwc 185 sc.

5 1/2 csg set at 4374 cw 150 sc cmt.

Filled 5 1/2 csg with sand (4360-90) and dumped 5 sx cmt with dump bailer (4360-20)

Recov. 2229' of 5 1/2 csg.

Pumped down 8 5/8 csg thru 8 5/8 plug container with 20 sc gel W/100 lbs hulls, plug and 125 sx 50-50 poz cmt. with 6% total gel. Max. pres. 500 lbs. SI pres. 100 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/19/68
INV. NO. 8304-W

Signed: Geo. F. Massey
Well Plugging Supervisor