

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 1 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beardmore Drlg. Co.

Complete Address 700 - 120 Bldg., Wichita, Kansas

Lease Name Mauch Well No. 1

Location NW SE Sec. 16 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4456

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated _____

Plugging Contractor Strata Drlg.

Address Wichita, Kansas License No. _____

Operation Completed: Hour 8:30A Day 28 Month 7 Year 1969

The above well was plugged as follows:

RTD 4456' 8 5/8 csg set at 449' cwc Gmt. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 430' set cementing plug and displaced 50 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/1/69
INV. NO. 211-W

Signed: Leo J. Massey
Well Plugging Supervisor