

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 9 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name R. V. Lehner

Complete Address: Box 398 Ness City, Kansas

Lease Name Petersille Well No. 5

Location C SW NE Sec. 13 Twp. 20 Rge. 24 (E) (W) XX

County Ness Total Depth 1449

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Strata Drlg.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 8:30A Day 7 Month 12 Year 1968

The Above well was plugged as follows:

RTD 1449' 8 5/8 csg set at 368' cwc. Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 330' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/9/68

INV. NO. 8973-W

Signed: Leo F. Massey  
Well Plugging Supervisor