

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUL 26 1966

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name R. V. Lehner

Complete Address: Box 398 Ness City Kansas

Lease Name Rollins Well No. 3

Location C SW SE Sec. 13 Twp. 20 Rge. 24 (S) (W) X

County Ness Total Depth 4415

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Strata Drlg. Co.

Address: Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 9 P Day 24 Month 7 Year 1966

The Above well was plugged as follows:

RTD 4415 8 5/8 set at 302 Ft. cwc 200 sc

Gunned pits, circulated heavy mud, set cementing plug at 600 Ft. and displaced

30 sc cement thru drill pipe. Heavy mud to 280 Ft. set cementing plug and displaced

20 sc cement thru drill pipe. Heavy mud to 40 Ft. set cementing plug, 1/3 sc hulls

and 10 sc cement to base of celler. Plugged rat and mouse hole with 5 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 7/26/66

INV. NO. 3628-u