

This well was a unpermitted SWD by Tomcat LTD. NO Docket # *R*

1 030575

15.145.20633.0000

API NUMBER 15- 145- 20, 633

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

05W, SEC. 7, T 20 S, R 20 W/E

1320 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5228

Lease Name Smith A Well # 3

Operator: Parrish Corp.

County Pawnee 144.79

Name & Address 100 South Market

Well Total Depth 4455 feet

Suite 200

Conductor Pipe: Size \_\_\_\_\_ feet

Wichita Ks. 67202

Surface Casing: Size 8 5/8 feet 450

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Parrish Corp License Number 5228

Address CO.

Company to plug at: Hour: 11:00 AM Day: 8 Month: 11 Year: 19 85

Plugging proposal received from Laverne Brown

(company name) Parrish Corp. (phone) 316-792-2621

were: 4 1/2" @ 4412 w/125 sx - Tubing & Packer stuck in hole -

top of pack @ ~ 1300' Tubing & Casing full of iron-sulfide.

1st plug - Shut hole w/ 2 qts nitro @ 1300' -> pump 125 sx  
down 4 1/2"

2nd plug - Squeeze annulus w/ 200 sx Shut in.

Plugging Proposal Received by Steve Dumont  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 PM Day: 8 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT

1st Shut hole in casing w/ 2 qts nitro - pump at a slow  
rate down 4 1/2 casing w/ 125 sx - started to get circulation  
of water at very end of cement.

2nd plug - pump 150 sx down annulus - 500 to 900 # psi all  
through-out - 3rd pump 35 sx back down 4 1/2" - 300-500 # to

Remarks: Squeeze 4 1/2, no recovery of casing  
(if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE DEC 10 1985

STATE CORPORATION COMMISSION Signed Steve Dumont  
(TECHNICIAN)

INV NO 11367

12-2-85  
DEC 2 1985