

To: 1 070303  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,093.0000  
SW SE NE, SEC. 16, T 20 S, R 23 W X  
3195 feet from S section line  
1050 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5046  
Operator: Raymond Oil Company Inc.  
Name & Address P.O. Box 48788  
Wichita, KS 67201

Lease Name Mauch Well # 1  
County Ness 143.78  
Well Total Depth 4424 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 474

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis Drilling Inc. License Number 5420  
Address Box 1586, Great Bend, KS 67530

Company to plug at: Hour: 6 p.m. Day: 12 Month: 2 Year: 19 87

Plugging proposal received from Dean Calvin  
(company name) Raymond Oil Company, Inc. (phone) 316-267-4214

were: to fill hole with heavy mud and spot cement through drill pipe. Anhydrite 1534-53'  
Elevation 2264' GL  
1st plug at 1560' with 50 sx cement, 2nd plug at 800' with 60 sx cement,  
3rd plug at 490' with 50 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 8 p.m. Day: 12 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1568' with 50 sx cement,  
2nd plug at 786' with 60 sx cement,  
3rd plug at 479' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
DATE 2-19-87  
INV. NO. 16160

STATE CORPORATION COMMISSION  
FEB 18 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Dan Godrow  
(TECHNICIAN)