

1090228

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,158.0000

SW, SEC. 35, T 20 S, R 19 W/E
1150 ESL feet from N SE Corner of XX section line
2800 FEV feet from W SE Corner of XX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9693

Lease Name Froetschner Well # 1

Operator: Carlile Drilling Co.

County Pawnee

Name & Address 901 Oil & Gas Building

Well Total Depth 4350 141.38 feet

Fort Worth, TX 76102

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor B & B Drilling License Number 5110

Address 515 Union Center, Wichita, KS 67202

Company to plug at: Hour: midnight Day: 5 Month: September Year: 19 84

Plugging proposal received from John Armbruster

(company name) B & B Great Bend (phone) 316-693-3329

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1320' with 50 sx cement

2nd plug at 480' with 70 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement
5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by R Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:00 am Day: 5 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1320' with 50 sx cement, 2nd plug at 480' with 70 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1984
9-11-84
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun # 19764

(If additional description is necessary, use BACK of this form.)

INVOICED

(copy / file not) observe this plugging.

DATE 9-17-84

Signed R Barluttan 510
(TECHNICIAN)

INV. NO. 3720 9-5 OCT 12 1984