


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pawnee County, Sec. 12 Twp. 20S Rge. 20 (E) (W)  
Location as "NE/CNW&SW&" or footage from lines SE SE NW  
Lease Owner Parker Petroleum, Inc.  
Lease Name Jennings Well No. 1  
Office Address Box 791 - Ponca City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-29 19 56  
Application for plugging filed 7-29 19 56  
Application for plugging approved 7-29 19 56  
Plugging commenced 7-29 19 56  
Plugging completed 7-29 19 56  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 4360 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	No Show	3713		10 3/4	255	
Toronto	"	3731				
Lansing	"	3758				
Cherokee	Slight Show	4188				
Mississippi	No Show	4327				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with mud to 240'. Plug set cemented with 15 sacks cement. Plug set at 50 feet cemented with 10 sacks of cement. Hole plugged.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SeRoBee Drilling Company, Inc.  
Address 521 Union National Bank Building - Wichita, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
Paul S. Septer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Paul S. Septer  
521 Union National Bank Bldg. - Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 56  
Ruth A. Carter  
Notary Public.

My commission expires October 23, 1958.

PLUGGING  
FILE SEC 12 T 20 R 20W  
BOOK PAGE 85 LINE 36

RECEIVED  
STATE

## SEROBEE DRILLING COMPANY, INC.

## JENNINGS #1

Company - Parker Petroleum, Inc.  
 Contractor - SeRoBee Drilling Company  
 Commenced - 7-7-56  
 Completed - 7-29-56  
 Total Depth - 4360'  
 Initial Prod. - D & A

Location: SE SE NW, Sec. 12-20S-20W,  
 Pawnee County, Kansas.  
 Elevation: 2230 DF  
 Casing: 10 3/4" - 255' cemented  
 W/125 sacks cement.

Figures Indicate Bottoms of Formations:

Depth	Formation
0 - 720	Shale & Shells
720 - 1040	Sand
1040 - 1265	Shale Red Shells
1265 - 1345	Shale Shells
1345 - 1440	Anhydrite & Shale
1440 - 1550	Shale Red Bed
1550 - 1850	Shale & Shell Red
1850 - 2065	Shale Lime Red Bed
2065 - 2190	Shale & Shells Lime
2190 - 2220	Lime Shale
2220 - 2280	Lime Light Hard
2280 - 2405	Lime & Shale
2405 - 2490	Lime
2490 - 2920	Lime & Shale
2920 - 2990	Lime Shale Brks.
2990 - 3200	Lime Shale
3200 - 3295	Shale Lime Strks.
3295 - 3495	Lime, Shale
3495 - 3505	Shale & Lime
3505 - 3770	Lime & Shale
3770 - 3820	Shale & Lime
3820 - 3854	Lime
3854 - 3935	Lime, Shale
3935 - 3985	Lime, Shale Brks.
3985 - 4013	Lime & Shale
4013 - 4037	Lime
4037 - 4085	Lime & Shale Brks.
4085 - 4140	Shale & Lime
4140 - 4202	Lime
4202 - 4225	Shale Lime
4225 - 4250	Shale Shells
4250 - 4288	Shale & Lime (Miss.)
4288 - 4360	Lime
4360 - R. T. D.	

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Jennings #1, located in the SE SE NW, Section 12-20S-20W, Pawnee County, Kansas.

SEROBEE DRILLING COMPANY, INC.

*Paul S. Septon*

Subscribed and sworn to before me this 31st day of July, 1956.

*Ruth H. Carter*  
 Notary Public

My commission expires October 23, 1958.

