

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

15-113-20438.0000

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-113-20 438 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Excalibur Production Co., Inc. OPERATOR'S LICENSE NO. 5330

ADDRESS Box 278 McPherson, Ks. 67460 PHONE # (316) 241-1265

LEASE (FARM) Alfred Nightingale WELL NO. 1 WELL LOCATION NE SW-SE COUNTY McPherson

SEC. 13 TWP. 20 RGE. 2W (E) or (W) TOTAL DEPTH 3430' PLUG BACK TD _____

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 130' CEMENTED WITH 75 SACKS

CASING SIZE 5 1/2" SET AT 3429' CEMENTED WITH 150 SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING WE WILL PLUG WELL ACCORDING TO THE RULES AND REGULATIONS OF THE STATE OF KANSAS.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? _____
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN _____ ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: 7-3-1990

Excalibur Production Co., Inc. PHONE # (316) 241-1265

ADDRESS Box 278 McPherson, Ks. 67460

PLUGGING CONTRACTOR Kelso Casing Pulling, Inc. LICENSE NO. 6050

ADDRESS P.O. Box 347 Chase, KS. 67524 PHONE # (316) 938-2943

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: [Signature]
(Operator or Agent)

DATE: 7-2-90

(2)

COMPANY: BLACKSTONE DRILLING, INC. 15.113.20438.0000
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: ALFRED NIGHTINGALE #1
 LOCATION: NE SW SE, Sec. 13-20-2W,
 McPherson County, Kansas
 COMMENCED: May 26, 1977
 COMPLETED: June 3, 1977
 ELEVATION:

0	to	95	Shale & Shells
95	to	130	Blue Shale
130	to	475	Shale
475	to	810	Shale & Lime
810	to	1225	Lime & Shale
1225	to	1665	Shale & Lime
1665	to	2310	Lime
2310	to	2330	Kansas City
2330	to	2945	Lime
2945	to	3205	Mississippi
3205	to	3300	Shale & Lime
3300	to	3396	Lime
3396	to	3400	Shale
3400	to	3430	Viola
		3430	T. D.

Cut 12 1/2" hole to 130' and run 130' of 8 5/8" surface pipe, cemented with 75 sacks of cement at 130'. Plug down at 1:30 P. M., May 26, 1977. Cut 7 7/8" hole to 3430'. Run 3433' of 5 1/2" casing, cemented 1' foot off bottom at 3429' with 150 sacks of cement. Plug down at 10:00 A. M., June 3, 1977.

Tops: Lansing - 2288' Conglomerate - 2903' Mississippi - 2928' Osage - 2958'
 Kinderhook - 3204' Viola - 3400'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on their Alfred Nightingale #1, located on the NE SW SE, Section 13-20-2W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

P. E. Plouffe
 P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas, this 3th day of June, 1977.

Johnnie L. Schmidt
 Johnnie L. Schmidt - Notary Public





Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
JACK SHRIVER	COMMISSIONER
JUDITH MCCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI FEIST ALBRECHT, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

July 25, 1990

Excalibur Production Co., Inc.
 Box 278
 McPherson, KS 67460

Alfred Nightingale #1
 NE SW SE 13-20-02W
 McPherson County, KS
 API No. 15-113-20,438

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
 Production Supervisor

District: #2, 202 W. First St., #304
 Wichita, KS 67202
 (316) 263 - 8809