

AUG 23 1949


15.113.00475.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

McPherson County. Sec. 35 Twp. 20 Rge. 1W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C of W Line W $\frac{1}{2}$ W $\frac{1}{2}$
Lease Owner W. L. Hartman
Lease Name Reimer Well No. 1
Office Address P. O. Box 54 Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-18-49 19
Application for plugging filed 8-18-49 19
Application for plugging approved 8-18-49 19
Plugging commenced 8-18-49 19
Plugging completed 8-18-49 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Durkey
Producing formation None Depth to top Bottom Total Depth of Well 3490 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
					160 Ft.	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Hole was filled to 155 feet with rotary mud. Plug set with 15 sacks of cement on top. Filled with Rotary mud 45 feet. 10 sacks of cement on top. Pipe cut off at bottom of cellar.

RECEIVED

Conservation Div.

AUG 24 1949

STATE CORPORATION
COMMISSION
KANSAS

W. L. Hartman

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to P. O. Box 54 Wichita, Kansas.
Address _____

STATE OF Kansas, COUNTY OF Barton, ss.
(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. C. Arnatt


(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 19 49

Altha L. Johnson
Notary Public.

My commission expires April 16, 1951

22-5133-s 9-48-10M



WELL LOG

15.113.00475.0000

Company: W. L. Hartman

Lease: Reimer #1

Contractor: H & H Drilling Company

Location: CWL W/2 W/2

Commenced: 8-7-49

35-20-1W

McPherson Co. Kansas

Completed: 8-18-49

Casing:

155' 8-5/8" cem. W/110 sax.

Elevation: 1522' df.

Potential: D&A

Formation	From	To	Remarks
Sandy Clay	0	100	
Shale	100	155	
Shale, Shells & Sand	155	700	
Shale & Shells	700	890	
Shale	890	1415	Slope Test - Ok SLM - Ok Trip @ 917'
Shale & Shells	1415	1530	
Shale & Shells	1530	1755	
Lime & Shale	1755	2013	Slope Test - OK SLM - Ok
Shale & Lime	2013	2140	1/2 Trip @ 2013' Circ. @ 2115 - No odor
Shale	2140	2250	
Lime	2250	2308	
Shale	2308	2325	
Lime & Shale	2325	2475	Circ. @ 2416 - No odor. 1/2 Trip
Lime	2475	2548	1/2 Trip Slope Test - Ok SLM - Ok
Lime & Shale	2548	2638	
Lime	2638	2772	1/2 Trip
Shale & Lime	2772	2895	Circ. @ 2895'
Lime	2895	2947	Circ. @ 2933 & 2940' - No odor
Lime - Miss. Chat	2947	2992	1/2 Trip
Lime - Miss. Chat	2992	3029	1/2 Trip
Lime	3029	3198	1/2 Trip 1/2 Trip 1/2 Trip
Lime & Shale	3198	3267	
Shale	3267	3349	1/2 Trip
Shale & Lime	3349	3465	Circ. @ 3465 - No odor - 1/2 Trip
Lime	3465	3490	Circ. @ 3490 - No odor
Total Depth	3490		

Geological Report

Drill Stem Test 2928-2940 - open 30 minutes - no blow. Recovered 5 feet mud.

Remarks: No showings were encountered to total depth. The well too low to warrant drilling to Arbuckle.

Tops: DERRICK FLOOR DATA (corrected two feet for rotary bushing)

Topeka	1749	227
Douglas sand	2092	570
Lansing-Kansas City	2311	789
Socoy Conglomerate	2888	1366
Socoy Conglomerate	2916	1394
Mississippian	2925	1403
Kinderhook shale	3219	1697
Viola	3442	1920
Simpson	3479	1957
Total Depth	3488	1966

RECORDED
AUG 31 1949
STATE OF KANSAS
COMMISSIONER
KANSAS

I hereby certify that this is a true and correct copy of the above log, to the best of my knowledge.

W. L. Hartman

Subscribed and sworn to before me this 28th day of August 1949

Georgias L. Laird
Notary Public

My Commission expires May 13, 1953

PLUGGING
FILE SEC 35 T 20 R 14
BOOK PAGE 110 LINE 22