

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-113-20,620-0000

LEASE NAME Vogts

#2
TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1
SW SW SW

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 9 TWP. 20 SRGE. 1W (NE or (W)

COUNTY McPherson

LEASE OPERATOR Krehbiel Oil

1343 N. Maple

ADDRESS McPherson, KS 67460

PHONE#(316) 241-3416 OPERATORS LICENSE NO. 5800

Date Well Completed

Character of Well Oil

Plugging Commenced 4/18/89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/21/89

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 2935'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	173	none
				5 1/2	2934	2111

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged bottom with sand to 2885', dumped 5 sacks cement, shot @2530',
2111', pulled pipe, set rock bridge @270', cemented top with 5 yards
slurry mix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Krehbiel Oil

STATE OF Kansas COUNTY OF Rice, ss. APR 26 1989 4-26-1989

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have the facts, statements, and matters herein contained and the log of the above-described well filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 25th day of April, 19 89

James Hoover
Notary Public

My Commission Expires:





Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250
 McPHERSON, KANSAS 67460

March 16, 1979

COMPANY: HOMER G. KREHBIEL, SR.
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: VOCTS #1
LOCATION: SW SW NW Section 9-20-1W,
 McPherson County, Kansas
COMMENCED: March 10, 1979
COMPLETED: March 16, 1979
ELEVATION:

0	to	130	Sand & Clay
130	to	490	Shale
490	to	580	Shale & Lime
580	to	935	Lime & Shale
935	to	1540	Shale & Lime
1540	to	1900	Lime & Shale
1900	to	2405	Shale & Lime
2405	to	2725	Lime
2725	to	2875	Lime & Shale
2875	to	2920	Shale
2920	to	2930	Mississippi
		2930	T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 25 1989
 CONSERVATION DIVISION
 Wichita Kansas

Cut 12 1/2" hole to 171' and run 173' of 3 1/8" surface pipe, cemented with 100 sacks of cement at 171'. Plug down at 1:45 P. M., March 10, 1979. Cut 7 1/8" hole to 2930'. Run 2934' of 5 1/2" casing, cemented 6" off bottom at 2929.5' with 50 sacks of cement. Plug down at 11:00 A. M., March 16, 1979.

TOPS: MISSISSIPPI - 2920'

Measurements taken from I. B.

CERTIFICATE

I, Charles D. Johnson, Secretary-Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Vogts #1, located on the SW SW NW Section 9-20-1W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

Charles D. Johnson, Secretary Treasurer

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 16th day of March, 1979.

Johnnie L. Schmidt - Notary Public

