


**WELL PLUGGING RECORD**

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

McPherson County, Sec. 4 Twp. 20 Rge. (E) 1 (W)  
Location as "NE/CNW/SW" or footage from lines NE - NE - SW  
Lease Owner Great Bend Pipe & Supply  
Lease Name Vogts Well No. 2  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 4-26 1960  
Plugging completed 4-28 1960  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	174	None
				5 1/2	3547	2122.09

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 2970' - dumped 5 sacks of cement - mudded to 170' - set 10' rock bridge - dumped 15 sacks of cement - mud to 35' - set rock bridge - dumped 8 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 10 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & D Casing Pulling Company License # 236  
Address Box 154 Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Nathan Meltzer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P. O. Box 191 - Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of May, 1960

My commission expires 3-30-61

Anne Meltzer Notary Public.



**GENSCH AND REISERER**  
PETROLEUM GEOLOGISTS  
525 PETROLEUM BLDG.  
AMHERST 2-0461  
AMHERST 2-6586  
WICHITA, KANSAS

15.113.00510.0000

December 15, 1955

Mr. Walt Clements  
Artnell Company  
Petroleum Building  
Wichita, Kansas

RE: Artnell #2 Vogts  
NE NE SW, Sec. 4-20S-1W  
McPherson County, Kansas

Dear Sir:

The following geological report on the captioned test includes sample analysis, drill stem tests and results, coring, and other remarks considered pertinent to the drilling of the well.

Commenced: 11-29-55 Contractor: Republic Drilling Co.  
Completed: 12-14-55

8 5/8 @163' with 125 sx 5 1/2" @3547 with 225 sx

Elevation: 1563 RB  
1561 DF

<u>Geological Tops</u>	<u>Samples</u>	<u>Electric Log</u>
Lansing		2345(-782)
Weathered Mississippi	2921(-1358)	2922(-1359)
Mississippi	2931(-1368)	2930(-1367)
Kinderhook		3195(-1632)
Chattanooga Shale	3427(-1864)	3427(-1864)
Misener Sand	3430(-1867)	3430(-1867)
Viola	3435(-1872)	3435(-1872)
Simpson Shale	3475(-1912)	3475(-1912)
Simpson Sand	3482(-1919)	3482(-1919)
Simpson Sand	3516(-1953)	3515(-1952)
Arbuckle	3544(-1981)	3543(-1980)
RTD	3555(-1992)	3554(-1991)

ZONES OF POROSITY WITH STAINING

MISSISSIPPI

2930-36 Samples poor-few pieces fine granular

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 22 1960

CONSERVATION DIVISION  
Wichita, Kansas