


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

McPherson County, Sec. 4 Twp. 20 Rge. (E) 1 (W)
Location as "NE/CNW/SW" or footage from lines SW - SW - SW
Lease Owner Great Bend Pipe & Supply
Lease Name L. Vogts Well No. 1
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 12-30 1958
Plugging completed _____ 1-8 1959
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	163	None
				5 1/2	3436	2116.67

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 2960' - dumped 5 sks cement - mudded to 160' - set 10' rock bridge - dumped 20 sks cement - mudded to 40' - set 10' rock bridge - dumped 10 sks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Co. License # 236
Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Nathan Meltzer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nathan Meltzer
Box 191, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of January 1959

My commission expires 3/30/61
Anne Meltzer Notary Public.

PLUGGING
FILE SEC. 4 T. 20 R. 1W
BOOK PAGE 6 LINE 19


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LEVITT & NATHAN
Farm- Vogts No. 1

SEC. 4 T. 20 R. 11
SW S1 SW

Total Depth. 3438
Comm. 8-17-53 Comp. 8-25-53
Shot or Treated.
Contractor. Fabco Drlg.
Issued. 10-17-53

County McPherson
KANSAS



Elevation. 1565
Production. 1,630,000 gas

CASING:

8 5/8" 153 cem. w/150 sx.
5 1/2" 3436 cem. w/125 sx.

Figures indicate Bottom of Formations.

sand & shale	163
sand, shale & shells	500
shale & shells	585
shale & lime	685
lime	830
shale & lime	1880
lime	1970
lime & shale	2005
shale	2370
lime & shale	2440
lime	2850
shale & lime	2920
lime	3191
lime & shale	3340
shale	3417
lime	3420
shale & lime	3438
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1958
CONSERVATION DIVISION
WICHITA, KANSAS

Tops: Scout	
Conglomerate	2927
Mississippi	2932
Kinderhook	3213
Viola	3435

D.S.T. 2934-90 - Sec. 2, 2,000,000 BHP 720
D.S.T. w/dbl packer. 2995-3011 lost mud
@ 3232
D.S.T. 3438

2932
1525
1367-

2970-90 1,630,000 BHP 760
2995-3011 9550 & 9077 BHP 720
3434-3438 430 Oil 340 Water BHP 910

Perf 2965-70 3,700,000

Bridge Plug AT 3010

PLUGGING
FILE SEC. 4 T. 20 R. 11 W
BOOK PAGE 6 LINE 19