

RECEIVED
STATE CORPORATION COMMISSION

15.113.20449.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Conservation Division
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

McPherson County, Sec. 5 Twp. 20S Rge. 1W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
SE SE NE


Lease Owner Eagle Resources, Inc.
Lease Name EYDON Becker Well No. 1
Office Address Box 352, CANTON, KS. 67428
Character of Well (Completed as Oil, Gas or Dry Hole)

GAS
Date Well completed 8-9 1977
Application for plugging filed 9-25 1980
Application for plugging approved 9-30 1980
Plugging commenced 10-3 1980
Plugging completed 10-8 1980
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top 2936 Bottom 2956 Total Depth of Well 3000
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	152'	- 0'
				4 1/2"	2998'	159'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

10-3-80 LEFT UNIT AT WELL
10-8-80 Rigged up. Dug cellar. Set floor.
Set Bottom Plug at 2900', 15' rock bridge, dumped 3 sacks Portland. Tacked & marked pipe. Dumped 16 barrels water, 10-7-80 Worked & Ripped pipe 5 pieces. parted 1620', 1410', 1200', 993' & 829' pipe parted. Pulled out 4 jts @ 159' & Layed down. 10-8-80 Tene floor down, set top plug, & bailed fluid down. & Filled with 18' rock bridge 4 & yards Ready Mix. Rigged down.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor TOWANDA Well Service INC.


STATE OF KANSAS COUNTY OF Butler, ss.
DONALD L. SIMMONS (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lewis C. Wilson
608 Main, Towanda, KS. 67144
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of October, 1980

Barbara D. Simmons
Notary Public.

My commission expires 6-30-81





Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

August 9, 1977

COMPANY: Carmon R. Decker
CONTRACTOR: Blackstone Drilling, Inc.
FARM: Eldon Becker #1
LOCATION: SE SE NE Section 5-20-1W,
 McPherson County, Kansas
COMMENCED: August 3, 1977
COMPLETED: August 9, 1977
ELEVATION:

0	to	100	Clay & Sand
100	to	155	Blue Shale
155	to	655	Shale & Lime
655	to	1325	Lime & Shale
1325	to	1690	Shale & Lime
1690	to	2285	Lime & Shale
2285	to	2425	Shale & Lime
2425	to	2835	Lime
2835	to	2956	Shale & Lime
2956	to	2984	Mississippi
2984	to	3000	Lime
		3000	T. D.

Drat 12" hole to 150' and run 152' of 8 5/8" surface pipe, cemented with 100 sacks of cement at 150'. Plug down at 11:00 A. M., August 3, 1977. Cut 7 7/8" hole to 3000'. Run 3003' of 4 1/2" pipe, cemented with 75 sacks of cement 2 foot off bottom at 2998'. Plug down at 8:30 A. M., August 9, 1977.

TOPS:

Measurements taken from K. B.

RECEIVED
 STATE CORPORATION COMMISSION

SEP 29 1980

CERTIFICATE

CONSERVATION DIVISION
 Wichita, Kansas

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is true and correct copy of log on your Eldon Becker #1, located on the SE SE NE, Section 5-20-1W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

P. E. Plouffe
 P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 9th day of August, 1977.

Johnnie L. Schmidt
 Johnnie L. Schmidt - Notary Public

JOHNNIE L. SCHMIDT
 McPherson County, Kansas
 My Appt. Exp. June 23, 1981