

15-051-02604-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Ellis County, Sec. 22 Twp. 13 Rge. 16 (E) (W) x
Location as "NE/CNW&SW&" or footage from lines C S/2 of SW/4
Lease Owner Louie M. Mai Operations
Lease Name Dknkel Well No. #6
Office Address Box 33, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4-21-67 19
Plugging completed 4-24-67 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3470'	260.03'
				8 5/8"	247'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3450', Mixed and ran 5 sacks cement thru dump bailer.
Mudded hole to 240', set 10' rock bridge. Mixed and ran 3 sacks of cement thru dump bailer.
Filled hole with 3 yards ready mix to base of cellar.

STATE CORPORATION COMMISSION

APR 27 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of April, 1967

Sidney D. Miller
Notary Public.

My commission expires 24 October 1968

15-051-02604-0000

LOUIS M. MAI OPERATIONS
DINKEL # 6

C S/2 SW/4 Sec. 22-13W-16W
ELLIS COUNTY, KANSAS

Total Depth: 3480'
Comm: 10-25-62
Comp: 11- 6-62

Casing

8 5/8" Set @ 247'
5 1/2" Set @ 3470'

Cement

175 sax of Pos. HA.5
100 sax of Pos. & 45 gal. Latex

Formation:	Depth:
Sand	30
Sandy Shale-Post Rock	160
Shale	565
Sand	715
Red Bed	1072
Anhydrite	1112
Shale-Sand	1770
Lime w/Shale Stks	1908
Lime	2250
Shale	2375
Lime-Shale	2550
Shale	2795
Lime-Shale	2988
Lime	3475
Sand	3480

RECEIVED
STATE COMMISSION
MAR 6 1967
OPERATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)SS
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Subscribed and sworn to before me this 18th day of December, 1962.

Notary Public

My commission expires: 1-8-66