


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

McPherson County. Sec. 16 Twp. 20S Rge. 2 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE  
Lease Owner National Associated Petroleum Company  
Lease Name #1 J. J. Goering Well No. 1  
Office Address 502 Ritz Building - Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed August 14 1953  
Application for plugging filed August 14 1953  
Application for plugging approved August 14 1953  
Plugging commenced August 14 1953  
Plugging completed August 14 1953  
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above  
Section Plot

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Depth to top Bottom Total Depth of Well 3036 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lans. - Kansas City	No shows	2336		10-3/4"	5 jts.	None
Mississippi	No shows	2985				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated on bottom for two hours with heavy mud  
Plugged back with heavy mud from a total depth of 3036' to 150'  
Set bridge plug at 150' spotted 20 sacks of cement through five joints of drill pipe.  
Plugged back to 125'.  
Filled with heavy mud from 125' to 10' from the surface of ground  
Set bridge plug at 10' and plugged back to surface with ten sacks of cement  
Surface pipe was cut off three feet below the surface of the ground and a steel cap was welded on casing.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to National Associated Petroleum Company  
Address 502 Ritz Building  
Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.  
J. A. Hayes, Jr. (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Hayes, Jr., Chief Geologist  
502 Ritz Building - Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of September, 1953

*Benjamin Eaton*  
Notary Public.

My commission expires November 18, 1956

**PLUGGING**  
FILE SEC 16 T 20 R 24  
BOOK PAGE 122 LINE 11

23-8278-s 4-50-10M

9-17-1953

NATIONAL ASSOCIATED PETROLEUM COMPANY  
J. J. GOERING NO. 1  
MC PHERSON COUNTY, KANSAS

Drilling Contractor: Exploration Drilling Co.  
220 North Boston  
Tulsa, Oklahoma

Started Rigging Up : 7-31-53  
Started Drilling : 7-31-53  
Completed Drilling : 8-14-53

Est: 5 Joints of 10-3/4" Surface Casing  
5/125 Sacks of Cement.

FORMATIONS

Surface	0'	150'
Shale, Shells & Red Rock	150	530
Lime & Shale	530	2080
Shale	2080	2215
Shale & Lime	2215	2510
Lime	2510	2580
Shale & Lime	2580	2980
Lime	2980	3096 Total Depth

CERTIFICATION

This is to certify that the above and foregoing is a true, correct, and complete copy of the Driller's Log covering the J. J. Goering No. 1 according to the records of this office and the best of my knowledge and belief.

EXPLORATION DRILLING COMPANY

By *George M. Steen*  
*W. C. Lewis*  
Notary Public

Subscribed and sworn to before me this 10th day of September, 1953.

My commission expires April 25, 1954.

**PLUGGING**  
FILE DEC 16 T 20 R 24  
PAGE 22 LINE 11

REMITTANCE ADVICE 15. 113. 30224. 0000  
**NATIONAL ASSOCIATED PETROLEUM COMPANY**

FIFTH FLOOR RITZ BUILDING  
 TULSA 3, OKLAHOMA

State Corporation Commission  
 Conservation Division  
 800 Bitting Building  
 Wichita, Kansas

DATE	AUDIT	REFERENCE	INVOICE AMOUNT	DISCOUNT	BALANCE
8'53 540	81		25.00+		25.00°

REC'D  
 STATE CORP COM  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

**PLUGGING**  
 FILE SEC 16-T 20-R 24  
 BOOK PAGE 122 LINE 11