





15.113.20713.0000

# Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250  
McPHERSON, KANSAS 67460

April 29, 1980

COMPANY: KERMIT SCHMIDT  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: ADAMS-STEVENSON #1  
 LOCATION: C NE SE Section 14-20-2W,  
 McPherson County, Kansas  
 COMMENCED: April 23, 1980  
 COMPLETED: April 28, 1980  
 ELEVATION: 1529'

0	to	15	Sand
15	to	105	Shale
135	to	428	Lime & Shale
428	to	2303	Shale & Lime
2303	to	2413	Lansing
2413	to	2780	Lime
2780	to	2931	Lime & Shale
2931	to	2925	Shale & Lime
2925	to	3002	Mississippi
3002	to	3002	T. D.

RECEIVED  
 STATE CONSERVATION COMMISSION  
 MAY 16 1980  
 CONSERVATION DIVISION  
 Wichita, Kansas

Cut 12 1/4" hole to 131' and run 133' of 8 5/8" surface casing, cemented with 170 sacks of cement at 131'. Plug down at 5:15 P. M., April 23, 1980. Hole dry and abandoned. Set bottom plug at 125' with 20 sacks of cement, filled with mud to 40' & set plug with 10 sacks of cement, 2 sacks in rathole. Plugging completed by State Plugger, Gilbert Towne, Holyrood, Kansas. Plugging completed by 10:00 P. M., April 28, 1980.

TOPS: LANSING 2303' MISSISSIPPI - 2925'

Measurements taken from K. B.

### CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Adams-Stevenson #1, located on the C NE SE Section 14-20-2W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 29th day of April, 1980.

Johnnie L. Schmidt - Notary Public

JOHNNIE L. SCHMIDT  
 McPherson County, Kansas  
 My Appt. Exp. June 23, 1981