

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

McPherson County. Sec. 25 Twp. 20 Rge. 2W (X) (W)

Location as "NE/CNWxSWx" or footage from lines. NW NW NE

Lease Owner A. Ainsworth

Lease Name John Well No. 1

Office Address 715 4th Nat'l Bk. Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed April 29, 19 63

Application for plugging filed April 29, 19 63

Application for plugging approved April 29, 19 63

Plugging commenced April 29, 19 63

Plugging completed April 29, 19 63

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones

Producing formation Depth to top Bottom Total Depth of Well 3588' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 180' - 20 sacks cement

Fluid to 30' - 8 sacks cement

2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Triangle Drilling Company

Address 324 N. Orchard El Dorado, Kansas

STATE OF _____, COUNTY OF _____, SS.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harry Hughes
324 N. Orchard El Dorado Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of August, 1963

My commission expires October 16, 1963

Notary Public.

Contractor - Triangle Drilling Co.
 Operator - A. Ainsworth
 Jahn #1 NW NW NE 25-20-2W
 McPherson County, Kansas

WELL LOG
 Started April 15, 1963
 Completed April 29, 1963
 R. T. D. 3588'

0	120	sand and gravel.
120	140	Blue Shale
140	216	shale
216	300	shale
300	350	shale
350	390	Anhydrite
390	650	shale and lime
650	732	lime
732	870	lime
870	960	lime
960	1100	shale
1100	1300	shale w/lime stks.
1300	1455	shale and lime
1455	1680	shale and lime
1680	1775	shale w/lime stks.
1775	1790	lime
1790	1940	lime and shale
1940	1955	lime and shale
1955	2025	lime
2025	2090	lime
2090	2200	shale w/lime stks.
2200	2321	shale and lime
2321	2435	lime and shale
2435	2443	lime
2443	2510	shale w/lime stks.
2510	2588	lime (KC)
2588	2630	lime
2630	2680	shale and lime
2680	2715	shale and lime
2715	2740	shale w/lime stks.
2740	2800	shale
2800	2874	shale
2874	2933	shale w/lime stks.
2933	2950	shale
2950	2985	lime (Miss)
2985	3033	lime
3033	3037	lime
3037	3071	lime
3071	3102	lime (Miss)
3102	3130	lime
3130	3143	shale and lime stks.
3143	3191	shale w/lime stks.
3191	3281	shale
3281	3382	shale

RECEIVED
 STATE CORPORATION COMMISSION

AUG 2 1963

CONSERVATION DIVISION
 Wichita, Kansas

Con't.

3382	3405	shale w/line stks.
3405	3413	shale
3413	3417	Viola
3417	3420	Viola
3420	3510	Simpson
3510	3535	line
3535	3508	ARB
3588		R. T. D.