


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Mc Pherson County, Sec. 24 Twp. 20S Rge. (E) 2 (W)
Location as "NE/CNW/SW" or footage from lines NW NE NE
Lease Owner Petroleum Management, Inc., for R. F. DUFFENS
Lease Name MEYER Well No. 1
Office Address 810 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 6-1 19 55
Application for plugging filed 8-29 19 55
Application for plugging approved 8-30 19 55
Plugging commenced 8-30 19 55
Plugging completed 9-6 19 55
Reason for abandonment of well or producing formation Non-Commercial
If a producing well is abandoned, date of last production 7-6-1955
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee
Producing formation Mississippi chert Depth to top 2935 Bottom 2991 Total Depth of Well 2991 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface pipe				8 5/8"	162'	all
Mississippi	oil & water	2935'	2991'	5 1/2"	2967'	2440'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand to 2930' dumped six sax cement on top. Mudded hole to 160' set 10' rock-bridge, dumped 15 sax cement. Mudded to 30' set rock bridge and capped with five sax cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John W. Ritchey (employee of ~~owner or leaseholder~~ operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John W. Ritchey
810 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of September, 19 55

My commission expires April 23, 1958

Mavis C. Murphy
Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 24 T 20 R 2W
BOOK PAGE 143 LINE 44

SEP 13 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
 NW SEC 24 120 R 2W
 BOOK PAGE 145 LINE 44

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 30 1955
 CONSERVATION DIVISION
 Wichita, Kansas

0-60	Sand
125	Shale
162	Shale & Shells
830	Shale & Lime
980	Lime & sand
1760	Shale & Shells
1810	Lime
1945	Lime & shale
2120	Lime
2307	Shale & Lime
2335	Lime
2380	Lime & shale
2633	Lime
2705	Shale
2920	Shale & Lime
2945	Lime & chert
2970	Mississippi "chat"
2974	Lime
2980	Sand
2992	Lime

8 5/8" Surface Casing -- 162' -- 140 sax common cement
 5 1/2" Prod. Casing ---2967 -- 50 sax common cement
 RTD -- 2970'
 TD -- 2992'

RICHARD-DUFFENS - MEYERS #1
 NW NE SEC. 24-20S-2W
 McPherson County, Kansas

Copy

15.113.06115.0000

ROTARY DRILLER'S LOG

Meyer # 1

Elevation #1550 Rotary Bushing

Location: NW of NE of NE, Sec. 24,
Twp 20S, Range 2W, McPherson Co., Ks.

Casing Record: 162: -8 5/8 with 140
sacks Bulk cement--
circulated-3%CC 2986'
with 50 sacks bulk
cement.

Operator: John Richard
Lawrence, Kansas.

Contractor: Salina Drilling Corp-
oration, Salina,
Kansas.

Well Commenced: April 7, 1955

Geologist: Willis D. Waterman,
Salina, Kansas.

Well Completed : April 16, 1955

Sand*****60

Shale*****125

Shale and Shells*****162

Shale and Lime*****830

Lime and Sand*****980

Shale and Shells*****1760

Lime*****1810

Lime and Shale*****1945

Lime*****2120

Shale and Lime*****2307

Lime*****2335

Lime and Shale*****2380

Lime*****2633

Shale*****2705

Shale and Lime*****2920

Lime & Chert*****2945

Mississippi*****2970

GEOLOGIST TOPS

Kansas City-----2307

Mississippi

PLUGGING
FILE SEC 24 T 20 R 2W
BOOK PAGE 145 LINE 44
2935

The above Rotary Drillers log is complete and correct to the best of my knowledge

Signed by Loren W. Hallam

Copy

Richard - Offens Drilling Co

15.113.06115.0000

CABLE TOOL LOG

2970 Rotary TD
from 2970 to 2974 hard lime
" 2974 " 2978 Sand Sho Oil & HFW of water
" 2978 " 2992 Lime Total Depth.

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1955
CONSERVATION DIVISION
WICHITA, KANSAS