

STATE OF KANSAS  
STATE CORPORATION COMMISSION

## WELL PLUGGING RECORD

**OR**

## FORMATION PLUGGING RECORD

**Strike out upper line  
when reporting plug-  
ging off formations.**

**Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas**

NORTH

A blank 4x4 grid with a small black dot in the top-left cell.

**Locate well correctly on above  
Section Plat**

McPherson County. Sec. 2 Twp. 20 Rge. (E) 2 (W)  
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NE NW  
Lease Owner. K. T. Anderson  
Lease Name. Koehn Well No. 1  
Office Address Emporia Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed Nov. 20 1946  
Application for plugging filed Nov. 20 1946  
Application for plugging approved Nov. 20 1946  
Plugging commenced Nov. 20 1946  
Plugging completed Nov. 20 1946  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production.....19.....  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well.....Ruell Durkee, McPherson, Kansas.  
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3439 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

### CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

Filled with 10<sup>4</sup> mud from 3439 ft. to 200 feet. Put in bridge and 20 sacks of cement on bridge. Mud put in to 15 feet and 5 sacks of cement cut off surface pipe at base of collar

(If additional description is necessary, use BACK of this sheet.)

Correspondence regarding this well should be addressed to.....K...T...Anderson  
Address.....Emporia, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.  
Emmett C. Veeder, ~~Notary Public~~ <sup>Notary Public</sup> and owner or operator of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed and that the same are true and correct. So help me God.

(Signature) By: Kenneth E. Veeder President.  
P. O. Box 201, Cherrivale, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of November, 1946.

My commission expires.....July 11, 1948.

.....  
Notary Public.

Veeder Supply &amp; Dev'l. Co.

Cherryvale, Kansas

Drilled for E. T. Anderson Farm Koehn (Deepening Job) No. 1 Depth 3439'  
 Contractor Veeder Supply & Development Company Pipe 100 ft. 10 3/4" Casing - 2913 ft. 72 casing  
 Location E/2 NW/4 Sec. 2 Twp. 20 Range 2  
 Commenced 11-12-46 Completed 11-20-46 County Mpherson State Kansas

FORMATION LOG

Iron	2959	2963	4
Iron & Lime	2963	2974	11
Lime	2974	2990	16
Cherty Lime & Iron	2990	3005	15
Lime	3005	3150	145
Shale	3150	3195	45
Muddy Shale	3195	3200	5
Blue Muddy Shale	3200	3240	40
Shale	3240	3280	40
Shale & Light Shells	3280	3335	55
Shale	3335	3380	45
Viola Lime	3380	3425	45
Lime	3425	3439	14

TOPS:

Kinderhook - 3150 ft. Shale  
 Viola - 3379 ft. Showing of oil- took drill  
 stem test - 200 ft. water  
 Simpson - 3428 ft. Sand - No shows, probable water

AFFIDAVIT

STATE OF KANSAS }  
 MONTGOMERY COUNTY } SS:

EMMETT C. VEEDER, of lawful age, being duly and solemnly sworn on oath  
 says:

I am a resident of Cherryvale, Montgomery County, Kansas and I hereby know  
 and on oath state, that the above drilling log covering the Koehn #1 well in  
 Section 2-20-2, Mpherson County, Kansas, is true and correct.  
 Further affiant saith not.

THE VEEDER SUPPLY &amp; DEVELOPMENT COMPANY,

By: Emmett C. Veeder  
 President

Subscribed and sworn to before me this 23rd day of November, 1946.

Edw. Louren  
 Notary Public

My Commission Expires, July 11, 1948

