


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas



Locate well correctly on above
Section Plat

McPherson County. Sec. 2 Twp. 20 Rge. 2 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW SE NW
Lease Owner George R. Hess
Lease Name Koehn #2 Well No. _____
Office Address McPherson, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 9-8-58 19____
Application for plugging filed 8-19-59 19____
Application for plugging approved 8-19-59 19____
Plugging commenced 8-20-59 19____
Plugging completed 8-26-59 19____
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 8 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation chert Depth to top 2928 Bottom 2993 Total Depth of Well 2993 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	167'	none
				5-1/2"	2980'	2617'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 2959' and found it open.
Filled w/sand to 2926' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" Casng.
Cleared hole and mudded the hole to 160', set rock bridge to 150' and dumped 15 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1959
CONSERVATION DIVISION
Wichita, Kansas

Plugging Completed

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 19 59

My commission expires 9-27-62

Thomas D. Dyer
Notary Public.

PLUGGING
FILE SEC. 2 T. 20 R. 2W
BOOK PAGE 62 LINE 19

COMPANY: George Hess
 CONTRACTOR: Mallard Drilling Company
 TAP: Koehn #2
 LOCATION: NW SE NW Sec. 2-20-2W
 Mc Pherson County, Kansas
 COMMENCED: September 2, 1958
 COMPLETED: September 8, 1958

0	to	80	Sand
80	to	167	Shale and shells
167	to	595	Shale and lime
595	to	810	Lime
810	to	1040	Lime and shale
1040	to	1775	Lime and shale
1775	to	1935	Lime
1935	to	2335	Lime and shale
2335	to	2560	Lime
2560	to	2680	Lime and shale
2680	to	2800	Shale and lime
2800	to	2928	Lime and shale
2928	to	2975	Mississippi
2975	to	2993	Mississippi
		2993	T.D. Rotary

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 24 1958
 CONSERVATION DIVISION
 Wichita, Kansas

Set 167 feet of 8 5/8" surface pipe. Cemented with 110 sacks cement.
 Set 5 1/2" at 2980. Cemented with 40 sacks cement.
 TOPS: Chat -- 2928
 Measurements taken from R.D.B. R.D.B. 5 1/2' from ground level.

C E R T I F I C A T E

I, G. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Koehn #2, Mc Pherson County, Kansas, as reflected by files of the Mallard Drilling Company.

G. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 13th day of September 1958.

E. W. Sage

My commission expires March 12, 1958

928-58
 P. Reforale 20 ft
 2935-2956
 sho oil & water
 600 gal acid & 1000 # sand
 could not get down all
 water & good sho gas will
 Recement
 Squeezed with 41 Sox
 new T.D 20509 by 2936 to 2958

LOGGING
 MC 2 T. 20 R. 20 W
 BOOK PAGE 62 LINE 18

COMPANY: George Hess
 CONTRACTOR: Mallard Drilling Company
 FARM: Koehn #2
 LOCATION: NW SE NW Sec. 2-20-2W
 Mc Pherson County, Kansas
 COMMENCED: September 2, 1958
 COMPLETED: September 8, 1958

0	to	80	Sand
80	to	167	Shale and shells
167	to	595	Shale and lime
595	to	810	Lime
810	to	1040	Lime and shale
1040	to	1775	Lime and shale
1775	to	1935	Lime
1935	to	2335	Lime and shale
2335	to	2560	Lime
2560	to	2680	Lime and shale
2680	to	2800	Shale and lime
2800	to	2928	Lime and shale
2928	to	2975	Mississippi
2975	to	2993	Mississippi
		2993	T.D. Rotary

RECEIVED
 STATE GEOLOGICAL COMMISSION
 SEP 10 1959
 CONSERVATION DIVISION
 Wichita, Kansas

Set 167 feet of 8 5/8" surface pipe. Cemented with 110 sacks cement.

Set 5 1/2" at 2980. Cemented with 40 sacks cement.

TOPS: Chat -- 2928

Measurements taken from R.D.B. R.D.B. 5 1/2' from ground level.

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Koehn #2, Mc Pherson County, Kansas, as reflected by files of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 13th day of September 1958.

Edward N. Sarge

My commission expires March 12, 1958

PLUGGING
 FILE SEC. 2 T. 20 R. 24
 BOOK PAGE 62 LINE 19