


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Mc Pherson County. Sec. 2 Twp. 20 Rge. 2W (~~2E~~) (W)
Location as "NE/CNW/SW" or footage from lines SW NW SW
Lease Owner Guy Finkle
Lease Name Steinbeck Well No. "C" 2
Office Address 222 East Kansas, Mc Pherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed July 6 67
Application for plugging approved July 8 19 67
Plugging commenced July 8 19 67
Plugging completed July 10 19 67
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2973' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2627'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with rock. Rock from 2973' to 2840'. Dumped 5 sx of cement. Mudded hole to 150'. Made 10' of rock bridge. Dumped 25 sx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the celler.

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2809 King St. Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12 th day of July, 19 67

My commission expires January 5, 1970
[Signature] Notary Public.

WELL RECORD

LEASE: Steinbeck "C"

WELL NO. 2

ELEVATION: 1536RB

LOCATION: SW NW SW
Sec. 2-20-2W

COMMENCED: 7/26/66

COMPLETED: 8/1/66

OPERATOR: Guy E. Finkle

CONTRACTOR: Melland Drilling Company, Inc.
Post Office Box 783
McPherson, KansasCASING RECORD: 8 5/8" @ 155'/105sx
5 1/2" @ 2973'/50sx

FORMATION	LOG	FORMATION	LOG
surface clay	40		
blue shale	115		
lime & shale	260		
lime	860		
lime & shale	1145		
shale & lime	1783		
lime & shale	2950		
Mississippi chert	2973		
RTD	2973		
Sample Tops			
Lansing	2303		
Mississippian	2950		

RECEIVED
STATE CONSERVATION COMMISSION
JUL 6 1967
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATE

State of Kansas, County of McPherson, ss.

I, Donald J. Melland, do hereby certify that the above is a true and correct copy of the log of the above named and described well, as reflected by the records of the Melland Drilling Company, Inc.

Donald J. Melland

Subscribed and sworn to before me, a Notary Public, in and for the County of McPherson, State of Kansas,
this 8th day of August, 1966.

My Commission expires December 23, 1967

W. B. D. [Signature]
Notary Public