


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

R
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Mc Pherson, County. Sec. 2 Twp. 20 Rge. 2w (E) (W)
Location as "NE/CNW%SW%" or footage from lines Sw NW NE
Lease Owner George Hess
Lease Name Decker Well No. 2
Office Address Mc Pherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Sept. 15 19 58
Application for plugging filed June 19 63
Application for plugging approved June 19 63
Plugging commenced June 12 19 63
Plugging completed June 25 19 63
Reason for abandonment of well or producing formation Went dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2951 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2145'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with rock. Rock from 2951' to 2930'. Dumped 5 sx of cement. Mudded hole to 165'. Made 10' of rock bridge. Dumped 20 sx of cement. Mudded hole to 29'. Made 5' of rock bridge. Dumped 8 sx of cement, filling to the bottom of the celler.

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address P.O. Box 983 Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 Kings Dr. Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of July 1963
Judy Lamb Notary Public.

My commission expires January 5, 1966

COMPANY: George Kees
 CONTRACTOR: Mallard Drilling Company
 FAULT: Decker #2
 LOCATION: SW NW NE Sec. 2-20-2W No Pherson County, Kansas
 COMMENCED: September 9, 1958
 COMPLETED: September 15, 1958

0	to	65	Sand
65	to	166	Shale and shells
166	to	545	Shale
545	to	750	Lime
750	to	955	Lime
955	to	1425	Shale
1425	to	1750	Lime and shale
1750	to	1870	Lime and shale
1870	to	2010	Lime
2010	to	2385	Lime and shale
2385	to	2625	Lime
2625	to	2735	Lime
2735	to	2910	Lime and shale
2910	to	2938	Lime and shale
2938	to	2951	Mississippi
		2951	T.D.

RECEIVED
STATE CORPORATION COMMISSION

JUN 13 1963

CONSERVATION DIVISION
Wichita, Kansas

Set 166 feet of 8 5/8" surface pipe. Cemented with 110 sacks cement.

Set 5 1/2" at 2940. Cemented with 40 sacks cement.

TOPS: 2296 -- K.C. 2938 -- Chat

Measurements taken from R.D.B. P.O.B. 5 1/2' from ground level.

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Decker #2, No Pherson County, Kansas, as reflected by files of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 17th day of September 1958.

Ernest V. Saag

My commission expires March 12, 1958