

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Mc Pherson County, Sec. II Twp. 20 Rge. 2W (E) (W)
Location as "NE/CNWxSWx" or footage from lines NW NE NE
Lease Owner George Hess
Lease Name Ratzlaff Well No. I
Office Address Mc Pherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed Dec 6 1961
Application for plugging filed January 1964
Application for plugging approved January 1964
Plugging commenced Jan 24 1964
Plugging completed Jan 28 1964
Reason for abandonment of well or producing formation Went dry.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation Depth to top Bottom Total Depth of Well 2971 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/8"		2,695'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with rock. Rock from 2971' to 2945'. Dumped 5 sx of cement. Mudded hole to 160'. Made 10' of rock bridge. Dumped 20 sx of cement. Mudded hole to 29'. Made 5' of rock bridge. Dumped 5 sx of cement, filling to the bottom of the celler.

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address P.O.Box 983 Hutchinson, Kansas


STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2809 Kings Dr. Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29 th day of January 19 64

My commission expires January 5, 1966

Notary Public.



Blackstone Drilling, Inc.

PEOPLES BANK BUILDING • PHONE CH 1-1265
McPHERSON • KANSAS

December 6, 1961

COMPANY:

GEORGE R. HESS

CONTRACTOR:

BLACKSTONE DRILLING, INC.

FARM:

RATZLAFF # 1

LOCATION:

NW NE NE, Sec. 11-20-2W
McPherson County, Kansas

COMMENCED:

NOVEMBER 30, 1961

COMPLETED:

DECEMBER 6, 1961

ELEVATION:

1548 K.B.

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1964

CONSERVATION DIVISION
Wichita, Kansas

0	to	10	Clay
10	to	35	Sand
35	to	145	Shale and Shells
145	to	585	Shale
585	to	790	Lime
790	to	2315	Shale and Lime
2315	to	2710	Lime
2710	to	2942	Lime and Shale
2942	to	2971	Mississippi
		2971	T. D.

MO-2-3707

Run 153.70' of 8 5/8" casing and cemented on bottom at 145' with 90 sacks of cement.
Run 2968.76' of 5 1/2" O.D. casing, cemented at 2957' - 14' off bottom with 35 sacks cement,
and one sack in rathole. Plug down at 3:30 A. M. December 6th, 1961. Bottom of
hole 2,971 feet. Spotted 40 barrels of oil behind pipe.

TOPS: Brown Lime - 2,255' K.C. - 2315' Mississippi - 2,942'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc., do hereby certify that the
above and foregoing is a true and correct copy of log on the Ratzlaff #1, Sec. 11-20-2W,
McPherson County, Kansas as reflected by files of the Blackstone Drilling, Inc.

H. J. Plouffe
H. J. Plouffe, Pres.

Subscribed and sworn to before me a Notary Public, within and for McPherson County,
Kansas this 8th day of December 1961.

Ruth Linholm
Ruth Linholm, Notary Public

My Commission Expires: 8/27/63