

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building,
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

MCPHERSON County. Sec. 12 Twp. 20 Rge. (E) 2 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NE NE
Lease Owner H. C. BENNETT
Lease Name E. MUNN Well No. 6
Office Address AUGUSTA, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 5/12/ 19 47
Application for plugging filed 5/12 19 47
Application for plugging approved 5/12 19 47
Plugging commenced 5/12 19 47
Plugging completed 5/12 19 47
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? YES

Name of Conservation Agent who supervised plugging of this well RUEL DURKEE
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3410' Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10 $\frac{3}{8}$ "	134'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED WITH HEAVY MUD - SET PLUG @ 200' - 20 SACKS CEMENT - FILLED WITH MUD:
TO 20' - PLUG AND 5 SACKS CEMENT.



(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to H. C. BENNETT
Address AUGUSTA, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. L. ROBERTS (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

RUSSELL, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 15TH day of MAY 19 47

[Signature]
Notary Public.

My commission expires 6/17/50

PLUGGING
FILE SEC-12-T-20-R-2W
BOOK PAGE 109 LINE 34

H. G. BENNETT
COUN #6

SEC. 12 Twp. 20 R2W. 2
COUNTY: McPHENSON, Ks.

TOTAL DEPTH: 3410'
COMM: 4/23/47 COMP: 5/12/47

6 JTS. 10 3/4" CASING SET AT 134'
CEMENT 90 SX

FORMATION:	DEPTH:
SURFACE CLAY	10'
SAND	30
SHALE	320
SHALE & ANHYDRITE	330
ANHYDRITE	360
SHALE & LIME	409
LIME	470
LIME & SHALE	545
SANDY LIME & SHALE	570
SHALE & LIME	590
LIME & SHALE BREAKS	640
SHALE & SHELLS	742
LIME & SHALE	780
SHALE	800
SANDY LIME	822
LIME & SHALE	885
SHALE	930
LIME & SHALE	965
SHALE & SHELLS	1045
SHALE & LIME	1895
LIME	2075
SAND & SHALE	2205
SHALE & LIME	2260
LIME	2500
SHALE & LIME	2920
SHALE	2936
CHAT	2993
CHAT & SHALE	3055
LIME	3083
CHERTY LIME	3095
LIME & SHALE	3170
SHALE	3205
SHALE & LIME	3389
VIOLA	3410

STATE OF KANSAS)
) SS
RUSSELL COUNTY)

MAY 16 1947

I HEREBY CERTIFY THAT THE ABOVE INFORMATION IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE.

Larry C. Froelich

SUBSCRIBED AND SWORN TO BEFORE ME THIS 15th DAY OF MAY, 1947.

Wesley L. ...
NOTARY PUBLIC

MY COMM. EXPIRES 6/17/50

PLUGGING
FILE SEC 12 T 20 R 2W
BOOK PAGE 109 INT. 84