

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 12 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Guy E. Finkle

Complete Address: 222 East Kansas Ave. McPherson, Kansas

Lease Name Steinbeck Well No. C-2

Location SW 1/4 SW Sec. 2 Twp. 20 Rge. 2 (E) (W)

County McPherson Total Depth 2973'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Art Lamb Casing Pulling

Address: Hutchinson, Kansas License No. # 440

Operation Completed: Hour 4 PM Day 10 Month 7 Year 67

The Above well was plugged as follows:

8 5/8"-155'-Circulated w/cement. 5 1/2"-2970'-Cemented. Top Perf. 2852'.

Sand hole to 2840'. 5 Sax.cement 2840' to 2790'. Mud 2790' to 150'.

Bridge 150' to 140'. 25 Sax.cement 140' to 65'. Mud 65' to 40'.

Bridge 40' to 30'. 10 Sax.cement 30' to 0. Pulled 2610'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Hugh Scott  
Well Plugging Supervisor

DATE 7/12/67

INV. NO. 5553-W