

RECEIVED

SEP 03 2004

KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-135-22016.0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

3/03

WELL OPERATOR Norstar Petroleum Inc. KCC LICENSE # 31652  
(owner/company name) (operator's)

ADDRESS 5 Inverness Drive East Suite 120 CITY Englewood

STATE CO ZIP CODE 80112 CONTACT PHONE # (303) 925-0696

LEASE Burditt WELL# 1 SEC. 21 T. 20 R. 23 (E/W/West)

C NE NW SPOT LOCATION/0000 COUNTY Ness

660 FEET (in exact footage) FROM X(N) (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM X(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 761 CEMENTED WITH 350 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 4498 CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4388-4396, 4294-4297, CIBP 4330

ELEVATION 2267/2272 T.D. 4500 PBDT 4330 ANHYDRITE DEPTH 1513  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING pump 200## of hulls and 25-35 sxs cmt. Cut & recover csg

(TOC=3482). Spot 50 sxs cmt @ Anhydrite, 80 sxs at bottom of surface csg., 40 sxs

at 350', 10 sxs at 40'. 60/40 w/ 6% gel

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Per Burchardt PHONE# (303) 925-0696

ADDRESS 5 Inverness Drive East ste 120 City/State Englewood, CO 80112

PLUGGING CONTRACTOR DS&W Well Service KCC LICENSE # 6901  
(company name) (contractor's)

6/03

ADDRESS POBox 231, Claflin KS 67525-0231 PHONE # (620) 587-3361

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Sep. 5, 2002

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8/27/02 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)



## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Norstar Petroleum, Inc.  
5 Inverness Drive East STE 120  
Englewood, CO 80112

September 04, 2002

Re: BURDITT #1  
API 15-135-22016-00-01  
NENW 21-20S-23W, 660 FNL 1980 FWL  
NESS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888