

1 070945

S-14

65

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19-145-21,190-0000

C W/2 NW, SEC. 29, T 20 S, R 20 W/2

3960 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5088

Lease Name Saxton Well # 1

Operator: John J. Darrah, Jr.

County Pawnee 146.25

Name & Address 412 E. Douglas, Suite One

Well Total Depth 4500 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1358

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 14 Month: 5 Year: 19 91

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering (phone) 316-792-2506

were: 5 1/2" at 4500' w/350 sx cement, PBD 4460', Perfs at 4306-10'

1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 14 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

and 150 sx cement down 8 5/8".

Maximum pressure 1400 psi and shut in 800 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1735' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 5-22-91

MAY 17 1991

INV. NO. 31864

CONSERVATION DIVISION
Wichita, Kansas

Signed Dan Darrah
(TECHNICIAN)