

1 090032

12-6

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-21,084-0000  
NE SE SW, SEC. 29, T 20 S, R 20 W/E  
990 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name Pelton Well # 1

Operator: Rains & Williamson Oil Company, Inc  
Name & Address 435 Page Ct., 220 W. Douglas  
Wichita, KS 67202

County Pawnee 141.37  
Well Total Depth 4350 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 455

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rains & Williamson Oil Company, Inc. License Number 5146

Address 435 Page Ct., 220 W. Douglas, Wichita, KS 67202

Company to plug at: Hour: 3:45 p.m. Day: 6 Month: 12 Year: 19 90

Plugging proposal received from Paul Stephens

(company name) Rains & Williamson (phone) 316-672-3287

were: 5 1/2" at 4349' w/100 sx cement, PBSD 4340', Perfs at 4301-11', Port collar at 1430'  
1st plug pump 2 sx hulls followed by 420 sx Halliburton lite cement. w/450 sx cem.

2nd plug pump 50 sx cement down backside.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:15 p.m. Day: 6 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 2 1/2 sx hulls down 5 1/2" casing, followed by 400 sx  
Halliburton Lite cement. Pumping pressure 0-1000 psi and shut in 750 psi.

Hooked up to backside, 250 pounds pressure in 2 seconds.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 10 1990 12-10-1990

Remarks: Used Halliburton lite cement by Halliburton. No casing recovery.  
(if additional description is necessary, use BACK of THIS FORM.)

INVOICED  
I hereby certify that I have observed this plugging.

Signed [Signature]  
(TECHNICIAN)

DATE 1-7-91

INV. NO. 30372

12-6