

1052395

TO: STATE CORPORATION COMMISSION

API NUMBER 15-145-20,257-0001
C SW NW SEC. 29, T 20 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME SAXTON WELL # 2 A

TECHNICIAN'S PLUGGING REPORT 5/30 COUNTY PAWNEE 39.00

OPERATOR LICENSE # 5088 WELL TOTAL DEPTH 1200 FEET

OPERATOR: JOHN J. DARRAH, JR. PRODUCTION CSG: SIZE 5 1/2" @ 1068' WITH 150 SX

NAME AND ADDRESS 225 N MARKET #300 SURFACE CASING: SIZE 8 5/8" @ 253' WITH 150 SX

WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D-19,009 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PLAINS, INC. LICENSE NUMBER 4072

ADDRESS PO BOX 346 NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 30 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) PLAINS, INC. (PHONE) 785-798-3995

WERE: PERFS AT 750-1050. PACKER LEFT IN HOLE AT 750'. CASING WAS TESTED TO 300 PSI.

PULLED TUBING LOOSE AT PACKER 750'. CIRCULATED 5 1/2" CASING FULL OF CEMENT THROUGH TUBING AT 750'

WITH 85 SX CEMENT. PULLED TUBING OUT OF HOLE. PUMPED DOWN 5 1/2" CASING WITH 25 SX CEMENT.

MAXIMUM PRESSURE 300 PSIG. SHUT IN 150 PSIG. PRESSURE 8 5/8" X 5 1/2" ANNULUS TO 300 PSIG. COULD

NOT PUMP IN ANY CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:49 PM DAY: 30 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT

PULLED TUBING LOOSE AT PACKER 750'. CIRCULATED 5 1/2" CASING FULL OF CEMENT THROUGH TUBING AT

750' WITH 85 SX CEMENT. PULLED TUBING OUT OF HOLE. PUMPED DOWN 5 1/2" CASING WITH 25 SX CEMENT

MAXIMUM PRESSURE 300 PSIG. SHUT IN 150 PSIG. PRESSURE 8 5/8" X 5 1/2" ANNULUS TO 300 PSIG. COULD

NOT PUMP IN ANY CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING

INVOICED SIGNED

DATE 6/9/00

WELL NO. 61848

Richard W. Lacey (TECHNICIAN)

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
JUN 2000
FORM CP 1/3