

To: 1121019 2-22
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,006.0000
W/2 SW NE, SEC. 31, T 20 S, R 20 W/EK
3300 feet from S section line
2130 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3831
Operator: Fritzlner Trucking, Inc.
Name & Address: P.O. Box 544
Ness City, KS 67560-0544

Lease Name Patmon Seelye B Well # 1
County Pawnee
Well Total Depth 4394 142.81 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 281

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 9:30 a.m. Day: 22 Month: 2 Year: 19 95

Plugging proposal received from Kevin

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

were: 5 1/2" at 4393' w/160 sx cement, PBTD 4390', Perfs at 4382-87'
1st plug sand back to 4320' and dump 5 sx cement on top of sand through bailer,
2nd plug rip casing at 615' and spot 60 sx cement at 615',
3rd plug rip casing at 320' and spot 50 sx cement,
4th plug cement 40' to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 1995
Richard Lacey
TECHNICIAN

Plugging Proposal Received by _____

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 22 Month: 2 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4320' and dump 5 sx cement on top of sand through bailer,
2nd plug ripped 5 1/2" casing at 615' and pumped 60 sx cement at 615', displaced the cement to 400' in 5 1/2" casing, pumped 5 sx gel ahead of the cement,
3rd plug ripped 5 1/2" casing at 320' and balanced 50 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 321' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Do not observe this plugging.

DATE 3-7-95

INV. NO. 42365

Signed Duane Rankin (TECHNICIAN)