

9-17-87

To: 1 070423
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA 15.145.30097.0000

SW NW, SEC. 31, T 20 S, R 20 W/E

3300 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Miller I Well # 1

Operator: Pickrell Drilling Company, Inc.

County Pawnee 143.00

Name & Address 110 North Market, Suite 205

Well Total Depth 4400 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12:15 p.m. Day: 17 Month: 9 Year: 19 87

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4390' Perfs at 4367-75'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 5 sx gel and 175 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 17 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 5 sx gel and 175 sx cement.

Maximum pressure 900 psi and shut in 500 psi.

9-22-1987
RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered approximately 450 lbs of casing. (if additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas

DATE 9-24-87

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 18230