

To: **1090522** *2-24*
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER **15-** 145-20,018 .0000

W/2 SE NE, SEC. 31, T. 20 S, R. 20 W/E

3300 feet from S section line

810 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3831

Lease Name Patmon Seelye B Well # 2

Operator: Fritzler Trucking, Inc.

County Pawnee

Name & Address P.O. Box 544

Well Total Depth 4372 *142.09* feet

Ness City, KS 67560-0544

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 9:45 a.m. Day: 24 Month: 2 Year: 1995

Plugging proposal received from Kevin

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Work: 5 1/2" at 4366' w/175 sx cement, Open hole 4366-72'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,

2nd plug perforate at 600', pump in 10 sx gel with 60 sx cement,

3rd plug fill 5 1/2" casing from 270' to surface with 27 sx cement,

4th plug pump 50 sx cement down backside.

RECEIVED
STATE CORPORATION COMMISSION
MAR 4 1995
CONSERVATION DIVISION
Steve Middleton
(TECHNICIAN)

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 24 Month: 2 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand through bailer,

2nd plug perforated 5 1/2" casing at 600'. Pumped in 10 sx gel with 60 sx cement, displaced out perms. Tried to rip casing at 270'. Would not come.

3rd plug hooked on to 5 1/2" casing and filled casing from 270' to surface with 27 sx cement. Casing stayed full. 4th plug pumped 50 sx cement down backside. Maximum pressure 150 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Steve Middleton (TECHNICIAN)

INVOICED
DATE: 3-7-95
INV. NO. 42366