

To: 1 060092 2-13
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 145-20,021-0000
C NE SE, SEC. 31, T 20 S, R 20 W/X
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name Chaddick A Well # 2
County Pawnee 142.42
Well Total Depth 4382 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address P.O. Box 628, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 13 Month: 2 Year: 19 98

Plugging proposal received from Ed Mondero

(company name) Pickrell Drilling Company, Inc. (phone) 785-798-2430

logs: 5 1/2" at 4381' w/160 sx cement, PBTD 4380', Perfs at 4374-78, 4363-64', CIBP at 4275'

1st plug pump 35 sx cement at 3660-3440', 2nd plug spot 35 sx cement from 3000-2680',

3rd plug perforate at 600', pump 80 sx cement over casing volume.

If it doesn't circulate, pump 100 sx cement down backside.

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 13 Month: 2 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug spot 35 sx cement at 3636',

2nd plug spot 35 sx cement at 3004',

Perforated at 600'. 3rd plug pumped 130 sx cement-didn't circulate.

Shut down, tied onto backside. 4th plug pumped 20 sx cement, pressured to 500# and held.

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1998
2-19-1998
CORRELATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE FEB 23 1998
I (did / did not) observe this plugging.

Signed Michael Maier (TECHNICIAN)

INV. NO. 50114 JUN 17 1998
2-13