

1 060486

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,186.0000

C E/2 SE , SEC. 30 , T 20 S, R 20 (WZK)

1320 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9883

Lease Name Pelton Well # 1

Operator: Sharon Resources, Inc.

County Pawnee 143.33

Name & Address 7100 E. Belleview Ave., Suite 201

Well Total Depth 4410 feet

Englewood, CO 80111

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 308 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 16 Month: February Year: 19 85

Plugging proposal received from Bruce Fickel

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1340' with 50 sx cement

2nd plug at 620' with 40 sx cement

3rd plug at 310' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement  
Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:15 am Day: 16 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1340' with 50 sx cement, 2nd plug at 620' with 40

sx cement, 3rd plug at 310' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 25 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton  
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

did not observe this plugging.

DATE 2-27-85

Signed Paul A. Luthi  
(TECHNICIAN)

INV. NO. 7179 2-16 MAR 26 1985

CARD MUST BE TYPED NOTICE OF INTENTION TO DRILL (see rules on reverse side) CARD MUST BE SIGNED

Starting Date: 2 7 85 month day year

API Number 15- 145-21,186

OPERATOR: License # 9883 Name Sharon Resources, Inc. Address 7100 E. Belleview Ave., Ste. 201 City/State/Zip Englewood, Colorado 80111 Contact Person Mr. Charles Dixon Phone 303-595-9111

C E/2 SE Sec 30 Twp 20S S. Rge 20W East West (location) 1320 Ft North from Southeast Corner of Section 660 Ft West from Southeast Corner of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5302 Name Red Tiger Drilling Company City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 660 feet. County Pawnee Lease Name Pelton Well# 1 Domestic well within 330 feet: [ ] yes [X] no Municipal well within one mile: [ ] yes [X] no

Well Drilled For: Well Class: Type Equipment: X Oil Snd Infield [X] Mud Rotary [ ] Gas Inj [X] Pool Ext [ ] Air Rotary [ ] OWWO [ ] Expl Wildcat [ ] Cable

Depth to Bottom of fresh water Lowest usable water formation Depth to Bottom of usable water Surface pipe by Alternate: Surface pipe to be set Conductor pipe if any required Ground surface elevation This Authorization Expires Approved By

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth Projected Total Depth Projected Formation at TD Expected Producing Formations

I certify that we will comply with K.S.A. 55-101, et seq., plus event... plugging hole to K.C. specifications.

Date 2/5/85 Signature of Operator or Agent

George A. Ogles OWNER BY RED TIGER DRILLING COMPANY

RECEIVED STATE CORPORATION COMMISSION FEB 25 1985 CONSERVATION DIVISION Wichita, Kansas