

1 080221

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,742-0000
150' N of C
NE NE , SEC. 30, T 20 S, R 20 W/E
4770 feet from N SE Corner of XXX section line
330 feet from W SE Corner of XXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Steffen Well # 2-E

Operator: Pickrell Drilling Company
Name & Address 110 N. Market, Suite 205
Wichita, KS 67202

County Pawnee 140.27

Well Total Depth 4316 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11:00 am Day: 21 Month: September Year: 19 84

Plugging proposal received from Byron Clawson

(company name) Rockhold (phone) 316-692-2506

were: 4 1/2" at 4309' Open Hole

1st plug sand back to 4250' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00 pm Day: 21 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4309' Open Hole

1st plug sanded back to 4250' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement.

Maximum pressure 800 psi and shut in pressure 450 psi

CONSERVATION DIVISION
Wichita, Kansas

Remarks: They recovered 2700' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

(If desired, you may observe this plugging.)

DATE 10-3-84

Signed J. A. Metz (TECHNICIAN) SD

INV. NO. 4007