

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21318-00-00
Spot: NENWNE Sec/Twnshp/Rge: 30-20S-20W
4950 feet from S Section Line, 1600 feet from E Section Line
Lease/Unit Name: PELTON Well Number: 1
County: PAWNEE Total Vertical Depth: 4343 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 215 WITH 175 SX CMT
Production: Size 5.5 feet: 4334 WITH 475 SX CMT
Liner: Size feet:

141.15

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/09/2001 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GEORGE STOEPPELWORT Company: JOHN HAY DARRAH, JR. Phone: (316) 263-2243

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. SPACER TO ANHYDRITE. CMT TO SURFACE. USED 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/09/2001 2:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:
OPEN HOLE FROM 4334-4343'. ANHYDRITE @ 1376'. LONG STRING CEMENTED WITH SPACER & CIRCULATED TO SURFACE. PUMPED DOWN 5 1/2" CASING WITH 200# HULLS - 25 SX CMT - 50 BBL OF GEL - 90 SX CMT. MAXIMUM PRESSURE 1000 PSIG. SHUT IN PRESSURE 800 PSIG. PRESSURE TESTED 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG.

INVOICED
3-20-2001
INV. NO. 2001061519

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.
Plugged through: CSG

District: 01 Signed Stacy Kussner (TECHNICIAN)

MAR 16 2001 RECEIVED
STATE CORPORATION COMMISSION
MAR 19 2001
CONSERVATION DIVISION

State Conservation Commission
200 Colorado Derby Building
Wichita, Kansas 67202

API Number 15-145-21-318-0000
LEASE NAME PELTON
WELL NUMBER 1
4950 Ft. From S. Section
Line
1600 Ft From E. Section
Line
SEC, 30 TWP. 20 RNG, 20W
(E) or (W)
COUNTY PAWNEE
Date Well Completed 4/4/90

Plugging Commenced 3/9/01
Plugging Completed 3/9/01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Comm. Div.
office within 30 days

OPERATOR: John J. Darrah, Jr.
ADDRESS: 225 N. Market, #300, Wichita, KS 67220
PHONE# (316) 26-2243 OPERATORS LICENSE NO: 5540~
Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on site
by Richard Lacey

KCC District Agent's Name

Is ACO-1 Filed? YES If not, is well log attached?
Producing formation Ft. Scott & Mississippi Depth to Top 4270 Bottom 4343 T.D. 4343
Show depth and thickness to all water, oil and gas formations

OIL, GAS OR WATER RECORDS		I		CASING RECORD		
Formation	Content	From	To	Size	Put In	Pulled OUT
Mississipian	oil /water	4334	4343	8 5/8	306	0
Ft. Scott		4270	4272	5 1/2	4334	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole, if cement or other plugs were used, state the character of same and depth placed, from ft to feet each set. Pressured 8 5/8 x 5 1/2 annulus to 500 psi & held for 15 minutes.
Pumped 25 sks 60-40 cement w/200# of hulls, 25 sx of bentonite gel, & 90 sks of 60-40 pozmix cement down casing to perfs and pressured to 900 psi. Held 800 psi.

Name of plugging contractor Swift Services License No. 32382
Address: P.O. Box 466, Ness City, KS 67560-0466
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John J. Darrah, Jr.


STATE OF Kansas COUNTY OF Sedgwick, ss.
George P. Stoepelwerth, AGENT
first being duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God

(Signature) George P. Stoepelwerth
(Address) 225 N. Market #301, Wichita

SUBSCRIBED AND SWORN TO before me this 12 day of March, 2001

Susan Utterback
Notary Public

My Commission Expires: 9/7/2002



RECEIVED
STATE CORPORATION COMMISSION

MAR 13 2001

CONSERVATION DIVISION
Wichita, Kansas

OR