

To: 1 060030
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202 15.145.19070.0000

API NUMBER 15- Spud date 5/11/80

C NW SE, SEC. 19, T 20 S, R 20 W/X
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5088
Operator: John J. Darrah Jr.
Name & Address: 225 N. Market, Ste. 300
Wichita, KS 67202

Lease Name Saxton A Well / 3
County Pawnee 141.12
Well Total Depth 4342 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 393

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 9:30 a.m. Day: 17 Month: 4 Year: 19 97

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

were: 4 1/2" at 4339' w/150 sx cement, Open hole
1st plug run tubing to 4200' and spot 20 sx cement and 1 sx hulls,
2nd plug perforate at 500' and fill with cement.

4-22-1997

RECEIVED
KANSAS
CORPORATION
APR 22 11:11 AM '97

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 17 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 4/16- Spotted 30 sx cement at 4339', Top plug from 840' up. DS&W
left casing ripper in hole, tubing jars and part of a sucker rod and 840' of cable on 4/16/97.
They used 300 sx 60/40 Pozmix, 3 1/2" hulls, and cemented through tubing but it didn't circulate.
Cement was down 180'.

4/17/97 Ran tubing down to 180' and cemented again with 15 sx 60/40 Pozmix 6% gel, then down
backside with 5 sx cement. Pressured to 500 psi and held.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (Agent/Operator) observe this plugging.

Signed Michael J. Mair (TECHNICIAN)

INVOICED
DATE 4-24-97
INV. NO. 48005
4-17