

1 060700

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 5-9-80

SE NE , SEC. 19, T 20 S, R 20 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5752

Lease Name Saxton "B" Well # 1

Operator: W. E. Carl-Hawn Brothers
Name & Address 1117 Centennial
Hays, KS 67601

County Pawnee
Well Total Depth 4349 141.34 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 425

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Ness County Well Service License Number 7527

Address P. O. Box J, Ness City, KS 67560

Company to plug at: Hour: 2:30 pm Day: 29 Month: October Year: 19 85

Plugging proposal received from Dennis Berry

(company name) W. E. Carl (phone) 913-628-8819

were: 4 1/2" at 4341' Open Hole from 4341-4349

1st plug sand back to 4290' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:45 pm Day: 29 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4290' and dumped 5 sx cement on top of sand through bailer, 2nd plug pumped through swedge with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, and 150 sx cement.

Maximum pressure 1200 psi and shut in 500 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
NOV 4 1985

RECEIVED
STATE CORPORATION COMMISSION
Signed Paul A. Luthis
(TECHNICIAN)

DATE NOV 4 1985

INV. NO. 10878

DEC 13 1985

NOV 1 1985 11-1-1985