

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-20652-00-00  
Spot: CNESE S Sec/Twnshp/Rge: 19-20S-20W  
1980 feet from X Section Line, 660 feet from E Section Line  
Lease/Unit Name: SAXTON A Well Number: 2  
County: PAWNEE Total Vertical Depth: 3318 feet

Operator License No.: 5088  
Op Name: DARRAH, JOHN JAY, JR.  
Address: 225 NORTH MARKET, STE 300  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 339 WITH 200 SX CMT  
Production: Size 4.5 feet: 4318 WITH 125 SX CMT  
Liner: Size \_\_\_\_\_ feet:

107.84

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2001 2:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GEORGE STOEPPELWORT Company: JOHN JAY DARRAH, JR Phone: (316) 263-2243

Proposed Plugging Method: PUMP 200# HULLS - 20 SX CMT. SPACER TO 600'. PERFORATE AT 600'. PUMP 80 SX CMT OVER CASING OR CIRCULATE. IF NO CIRCULATION PUMP 150 SX DOWN 8 5/8 X 4 1/2.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/09/2001 4:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE AT 4318-30'. PUMPED DOWN 4 1/2" CASING WITH 200# HULLS - 20 SX CMT - 20 SX GEL. DISPLACED CMT TO 4200'. MAXIMUM PRESSURE 900#. SHUT IN PRESSURE 400#. PERFORATED 4 1/2" CASING AT 600'. PUMPED 135 SX CMT DOWN 4 1/2" CASING. MAXIMUM PRESSURE 600#. SHUT IN PRESSURE 50#. PUMPED 10 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 500#.

INVOICED  
DATE 3-20-2001  
TOTAL DOLLARS 2001061519

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Steve A. Hurant for RUC  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
Form CP-2/3  
MAR 16 2001

MP

MAR 19 2001  
3-19-2001  
CONSERVATION DIVISION  
11588

State Conservation Commission  
200 Colorado Derby Building  
Wichita, Kansas 67202

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Comm. Div.  
office within 30 days

API Number 15-145-20652 -00-00  
LEASE NAME SAXTON  
WELL NUMBER 2  
1980 Ft. From S. Section  
Line  
660 Ft From E. Section  
Line  
SEC, 19 TWP. 20 RNG, 20W  
E) or (W)  
COUNTY Pawnee  
Date Well Completed  
11/18/80  
Plugging Commenced 3/9/01  
Plugging Completed 3/9/01

OPERATOR: John J. Darrah, Jr.  
ADDRESS: 225 N. Market, #300, Wichita, KS 67220  
PHONE# (316) 26-2243 OPERATORS LICENSE NO: 5540~  
Character of Well OIL  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on site  
by Richard Lacey

KCC District Agent's Name

Is ACO-1 Filed? YES If not, is well log attached?  
Producing formation Mississippian Death to Top 4318 Bottom 4330 T.D. 4330  
Show depth and thickness to all water, oil and gas formations

OIL, GAS OR WATER RECORDS			CASING RECORD			
Formation	Content	From	To	Size	Put In	Pulled OUT
<u>Mississippian</u>	<u>oil/water</u>	<u>4318</u>	<u>4330</u>	<u>8 5/8</u>	<u>339</u>	<u>0</u>
				<u>4 1/2</u>	<u>4318</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole, If cement or other plugs were used, state the character of same and depth placed, from ft to feet each set. Pumped 20 sks 60-40 pozmix cement with 200 # of hulls, 15 saks of bentonite gel, and 10 bbls of water down casing @ 3 bpm & 400 psi decreasing to 1.5 bpm @ 900 psi. ISIP 900psi, 10 min 50 psi. Wait 45 min for perforators, hole standing full, perf'd @600' w/ 4, pumped 135 sx 60-40 poz to max of 400 psi. Slow decline in pressure. Pumped 2 1/2 bbls (20 sx) 60-40 pozmix down 8 5/8 x 4 1/2" annulus to max pressure of 500 psi, held.

Name of plugging contractor Swift Services  
Address P.O. Box 466, Ness City, KS 67560-0466  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John J. Darrah, Jr.

License No. 32382

STATE OF Kansas COUNTY OF Sedgwick, ss.

George P. Stoeppelwerth, Agent of Operator, of above described well, first being duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) George P. Stoeppelwerth


Address) 225 N. Market, #300, Wichita

SUBSCRIBED AND SWORN TO before me this 12 day of March , 2001

Susan Utterback

Notary Public

My Commission Expires: 9/7/2002



RECEIVED  
STATE CORPORATION COMMISSION

MAR 13 2001

CONSERVATION DIVISION

OR