

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20617-00-00
Spot: CSESE Sec/Twnshp/Rge: 19-20S-20W
660 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: SAXTON Well Number: 1
County: PAWNEE Total Vertical Depth: 4322 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet: 8 1/40.47
Surface Casing: Size 8.625 feet: 289
Production: Size 4.5 feet: 4308
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/26/2001 9:30 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: GEORGE STOPPLEWORTH Company: JOHN JAY DARRAH, JR Phone: (316) 263-2243

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING METHOD.

Plugging Proposal Received By: Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/04/2001 10:40 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE FROM 4308-4322'. SFL @1700'. PUMPED DOWN 4 1/2" WITH 200# HULLS - 20 SX CMT DISPLACED TO 4000'. PERFORATED 4 1/2" AT 1400' & 600'. HAD CEDAR HILLS FLOW TO SURFACE. RAN TUBING TO 1400' CIRCULATED CMT TO SURFACE UP 4 1/2" WITH 110 SX CMT. PULLED TUBING. PRESSURED 8 5/8" X 4 1/2" ANNULUS TO 500# NO MOVEMENT. PUMPED 40 SX CMT DOWN 4 1/2". 8 5/8" X 4 1/2" ANNULUS FLOWED 3-4 BBL. ON 10/4/01 TIED ONTO BACKSIDE AND PUMPED 135 SX CMT. MAXIMUM PRESSURE 875#. SHUT IN WITH 400#. TOP 4 1/2" CASING WITH 15 SX CMT. MICHAEL MAIER WITNESSED REMAINING PLUGGING PROCEDURE ON 10/04/01.

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERY.

Plugged through: CSG

District: 01

RECEIVED

OCT 15 2001

KCC WICHITA

Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE

10-15-01

DIV. NO.

2002060809

OCT 05 2001

ML

Form CP-2/3