

1052394

TO STATE CORPORATION COMMISSION

API NUMBER 15-145-20,753-0000
E/2 SW SW SEC. 19, T 20 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SAXTON WELL # 4

TECHNICIAN'S PLUGGING REPORT

COUNTY PAWNEE

140.34

OPERATOR LICENSE # 5088

WELL TOTAL DEPTH 4318 FEET

OPERATOR: JOHN J. DARRAH JR.

PRODUCTION CSG: SIZE 4 1/2" @ 4309' WITH 150 SX

NAME AND 225 N MARKET #300

SURFACE CASING: SIZE 8 5/8" @ 291' WITH 200 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL INPUT WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

RECEIVED JUN 6 2000
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING CONTRACTOR PLAINS, INC.

LICENSE NUMBER 4072

ADDRESS PO BOX 346, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 30 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) PLAINS, INC. (PHONE) 785-798-3995

WERE: OPEN HOLE AT 4309-4318 SQUEEZED @ 2600'. WELL HAD CASING LEAKS @ 800' SQUEEZED AT 800-260

PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 40 SX CEMENT. PRESSURED TO 300 PSIG. SHUT IN AT 300 PSIG.

PUMPED DOWN 2 3/4" TUBING INSIDE OF 4 1/2" AT 500' WITH 300# HULLS & 410 SX CEMENT. LOST CIR-

CULATION AFTER 100 SX CEMENT. LET CEMENT SET FOR 3 1/2 HOURS. TAGGED CEMENT AT 502' WITH

TUBING. CIRCULATED CEMENT TO SURFACE DOWN 500' OF TUBING. PULLED TUBING & TOPPED OFF WELL.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 30 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT

PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 40 SX CEMENT. PRESSURED TO 300 PSIG. SHUT IN AT 300 PSIG.

PUMPED DOWN 2 3/4" TUBING INSIDE OF 4 1/2" AT 500' WITH 300# HULLS & 410 SX CEMENT. LOST CIRCU-

LATION AFTER 100 SX CEMENT. LET CEMENT SET FOR 3 1/2 HOURS. TAGGED CEMENT AT 502' WITH TUBING.

CIRCULATED CEMENT TO SURFACE DOWN 500' OF TUBING. PULLED TUBING & TOPPED OFF WELL.

REMARKS: USED 60/40 POZMIX 6% GEL & COMMON CEMENT BY SWIFT SERVICES. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

SIGNED

Richard W. Lacey

(TECHNICIAN)

FORM CP-2/3

DATE 6/9/00

INV NO 61848

State Conservation Commission
200 Colorado Derby Building
Wichita, Kansas 67202

API Number 15-145-20753 • 0000
LEASE NAME Saxton
WELL NUMBER 4
660 Ft. From S. Section Line
1650 Ft From E. Section
Line
SEC 19 TWN 20 RNG 20 WEST
Pawnee COUNTY
Date Well Completed

TYPE OR PRINT
NOTICE: Fill out completely
and return to Comm. Div.
office within 30 days

OPERATOR: John J. Darrah, Jr.
ADDRESS: 225 N. Market, #300, Wichita, KS 67220
PHONE# (316) 26-2243 OPERATORS LICENSE NO: 5540-5088
Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 5/30/00
Plugging Completed 5/30/00

The plugging proposal was approved on 5/30/00
by Richard Lacey KCC District Agent's Name
Is ACO-1 Filed? YES If not, is well log attached?
Producing formation Mississippian Depth to Top 4309 Bottom 4318 T.D. 4318 ft.
Show depth and thickness to all water, oil and gas formations

OIL, GAS OR WATER RECORDS		I			CASING RECORD	
Formation	Content	From	To	Size	Put In	Pulled OUT
Mississippi	Water/oil	4309	4318	8 5/8	291	0
				4 1/2	4309	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole, if cement or other plugs were used, state the character of same and depth placed, from ft to feet each set.
Pumped 40 sx. 60-40 pozmix into 8 5/8" x 4 1/2" annulus. Pumped 410 sx. 60-40 pozmix, left standing, returned four hours later, pumped 70 sx common to fill hole, pulled 17 joints (all) 2 3/8" kill string and pumped 5 sx common to fill hole.


Name of plugging contractor Plains Well Service/Swift Services License No. 4072
Address P.O. Box 346, Ness City/ P.O. Box 466, Ness City
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John Jay Darrah, Jr.

STATE of Kansas, COUNTY OF Sedgwick, ss.
G.P. Stoepelwerth (Employee of Operator or Operator) of above-described well, first being duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God~

(Signature) [Signature]
(Address) 225 N. MARKET #300
WICHITA, KS

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 2000

[Signature] Notary Public



My Commission Expires: 9/7/02

RECEIVED
STATE CORPORATION COMMISSION
JUN 2 2000
CONSERVATION DIVISION
Wichita, Kansas