

To: 1 051481
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-10
API NUMBER 15- 145-20,878.0000 82 R

TECHNICIAN'S PLUGGING REPORT
Operator License # 30705
Operator: B-Y Operating, Inc.
Name & Address: 251 N. Water, Suite 12
Wichita, KS 67202

NE NW NE, SEC. 18, T 20 S, R 20 W/E
4950 feet from S section line
1650 feet from E section line
Lease Name Vandenberg Well # 1
County Pawnee 141.96
Well Total Depth 4368 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 287

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 10 Month: 10 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4367' w/75 sx cement, Open hole
1st plug sand back to 4310' and dump 5 sx cement on top of sand through bailer,
2nd plug shoot at 600' and pump 200 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 10 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4310' and dumped 5 sx cement on top of sand through bailer,

Shot went off prematurely and shot casing off at 300'.

2nd plug pump 1/2 sx hulls and 200 sx cement.

Maximum pressure 900 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 300' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 10-29-91

WV. NO. 33537

Signed Richard M. Lacey (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1991
DIVISION