

7-14-88

1 051069

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,268.0000

NW NW, SEC. 21, T 20 S, R 23 W/E EX

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6040

Lease Name Burditt Well # 1

Operator: Bankoff Oil Company

County Ness 143.98

Name & Address Box 700657

Well Total Depth 4430 feet

Tulsa, OK 74170

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 294

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 2:30 a.m. Day: 14 Month: 7 Year: 19 88

Plugging proposal received from Wilmer Dreiling

(company name) Abercrombie Drilling (phone) 316-262-1841
Elevation 2264'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1508-29'

1st plug at 1530' with 50 sx cement, 2nd plug at 800' with 80 sx cement,

3rd plug at 300' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5 a.m. Day: 14 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,

2nd plug at 800' with 80 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If not observed) observe this plugging.

DATE 7-21-88

Signed Richard M. Lacey
(TECHNICIAN)

INV. NO. 21504

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date 07/05/88 month day year

API Number 15-135-23,268.0000

OPERATOR: License # 6040 Name BANKOFF OIL COMPANY Address BOX 700657 City/State/Zip TULSA, OKLAHOMA 74170 Contact Person FRANK S. MIZE Phone (316) 262-2784

NW NW Sec. 21 Twp. 20 S, Rg. 23 East X West 4620 Ft. from South Line of Section 4620 Ft. from East Line of Section

CONTRACTOR: License # 5422 Name ABERCROMBIE DRILLING City/State WICHITA, KANSAS 67202

(Note: Locate well on Section Plat on reverse side)

Well Drilled For: X Oil Storage Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO X Expl X Wildcat Cable

Nearest lease or unit boundary line 660 feet County NESS Lease Name BURDITT Well # 1 Ground surface elevation N/A feet MSL Domestic well within 330 feet yes X no Municipal well within one mile yes X no Depth to bottom of fresh water 75 Depth to bottom of usable water 350 Surface pipe by Alternate 1 X Surface pipe planned to be set 280 Conductor pipe required 4450 Projected Total Depth 4450 feet Formation MISSISSIPPIAN

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq, plus eventually plugging hole to KCC specifications. Date 06/28/88 Signature of Operator or Agent Frank S. Mize Title EXPLORATION MGR

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2 This Authorization Expires 12-30-88 Approved By R. H. G. 6-30-88

EFFECTIVE DATE: 7-5-88

SPUD 7-5-88

NW NW Sec. 21 Twp. 20 S, Rg. 23 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (ft), Formation, and Material (e.g., 60-40 POZ, 6% GEL). Includes entries for 1st through 5th plugs and Rathole to surface minus 5 feet.

Log entries including: PUSHER Wilber Drating, TD 4430' FORMATION Miss, SURFACE PIPE 8 5/8" @ 294', ANHYDRITE 1508' ELEVATION 22616L, STARTING TIME & DATE 2:30 AM 7-14-88, COMPLETION TIME & DATE 5:00 AM 7-14-88, 1st PLUG @ 1530 FT. W/ 50 SX, 2nd PLUG @ 800 FT. W/ 80 SX, 3rd PLUG @ 300 FT. W/ 40 SX, 4th PLUG @ 40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY Allied 60/40 SR, TECHNICIAN R.L. D.G.