

1 070271

DEC 22 1986

15.135.20676.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 150' NW C SE SW SEC. 21, T 20 S, R 23 W X
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A
735 feet from S section line
3375 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Petersilie "A" Well # 1

Operator: Donald C. Slawson

County Ness 144.30

Name & Address 200 Douglas Building

Well Total Depth 4440 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 355

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 22 Month: 12 Year: 19 86

Plugging proposal received from Ron Hoover

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4439' Perfs at 4329-35' Elevation 2233' K.B.

1st plug sand back to 4270' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:20 a.m. Day: 22 Month: 12 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 4270' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release 8 5/8" wiper plug and pump 150 sx cement.

STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 200 psi.

DEC 31 1986

Remarks: Recovered 2800' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

12-31-1986

INVOICED
(date) observe this plugging.

Signed Dan Fortman (TECHNICIAN)

DATE 1-5-87

INV. NO. 15767