

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22016-00-01
Spot: NENW Sec/Twnshp/Rge: 21-20S-23W
660 feet from N Section Line, 1980 feet from W Section Line
Lease/Unit Name: BURDITT Well Number: 1
County: NESS Total Vertical Depth: 4500 feet
Conductor Pipe: Size feet: 8 1/4 - 25
Surface Casing: Size 8.625 feet: 761 WITH 350 SX CMT
Production: Size 4.5 feet: 4498 WITH 200 SX CMT
Liner: Size feet:

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 5 INVERNESS DRIVE EAST STE 120
ENGLEWOOD, CO 80112

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/30/2003 9:15 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVE PAULY Company: NORSTAR PETROLEUM Phone: (303) 925-0696

Proposed Plugging Method: PUMP 25 SX CMT WITH 200# HULLS FOLLOWED BY 50 BBL MUD & 14 BBL WATER. PRESSURE TEST. PERFORATE AT 790' & PUMP 205 SX CMT. CIRCULATE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/30/2003 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:


PBTD 4330'. PERFS AT 4388-4396 & 4294-4297'. CIBP @ 4330'. PUMPED DOWN 4 1/2" 25 SX CMT WITH 200# HULLS FOLLOWED BY 50 BBL MUD & 14 BBL WATER. MAXIMUM PRESSURE 1200#. PERFORATED AT 790'. PUMP 205 SX CMT DOWN CASING & CIRCULATED AROUND BACKSIDE.

RECEIVED
FEB 07 2003
KCC WICHITA
2-7-2003

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICED
DATE 2-10-03
INV. NO. 2003061173

Form 10-2/3